BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Name of Work :- Filling of pot holes in main and cross roads of Dasarahalli Ward No.15, T.Dasarahalli Sub Division.

Est. Cost Rs 10.00 Lakhs

Sl	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.155 I No.20.18)								
	Coconut Garden	Cum	5	3.00	3.00	0.20	9.00		
	Officers Model Colony		5	3.00	3.00	0.20	9.00		
			4	2.50	3.00	0.20	6.00		
	Kempe gowda Nagara cross roads		4	2.80	2.40	0.20	5.38		
	KK road		4	2.50	2.50	0.20	5.00		
	St.Marys School road		6	3.00	3.00	0.20	10.80		
	S Ramesh road		3	2.50	2.40	0.20	3.60		
	Bhuvaneshwari Nagara & Cross road		4	3.00	3.00	0.20	7.20		
			5	2.50	2.00	0.20	5.00		
	Kalasti Nagara		3	3.00	3.00	0.20	5.40		
			3	2.60	2.70	0.20	4.21		
	Bad Reaches								
	Excl Kalyana Mantapa road		1	35.00	6.00	0.20	42.00		
	Bharathi theater road		1	35.00	5.50	0.20	38.50		
	Nrupatunga Road Entrance		1	18.00	5.00	0.20	18.00		
	Dharmastala hotel road entrance		1	22.00	6.00	0.20	26.40		
			1	16.78	5.50	0.20	18.46		
							213.95	2001.28	428166.00

Sl	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Basic Rate	1888.00							
	Add Area Weightage 6%	113.28							
	Total	2001.28							
2	KSRRB 3000 Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, applying tack coat on the sides and base of excavation at 2.5kg/10sqm as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 3004.2								
	Coconut Garden	SQM	5	3.00	3.00		45.00		
	Officers Model Colony		5	3.00	3.00		45.00		
			4	2.50	3.00		30.00		
	Kempe gowda Nagara cross roads		4	2.80	2.40		26.88		
	KK road		4	2.50	2.50		25.00		
	St.Marys School road		6	3.00	3.00		54.00		
	S Ramesh road		3	2.50	2.40		18.00		
	Bhuvaneshwari Nagara & Cross road		4	3.00	3.00		36.00		
			5	2.50	2.00		25.00		
	Kalasti Nagara		3	3.00	3.00		27.00		
			3	2.60	2.70		21.06		
	Bad Reaches		0	0.00	0.00				
	Excl Kalyana Mantapa road		1	35.00	6.00		210.00		
	Bharathi theater road		1	35.00	5.50		192.50		
	Nrupatunga Road Entrance		1	18.00	5.00		90.00		
	Dharmastala hotel road entrance		1	22.00	6.00		132.00		
			1	16.78	5.50		92.29		
							1069.73	365.70	391200.00
	Basic Rate	345.00							
	Add Area Weightage 6%	20.70							
	Total	365.70							
							Sub Total		819366.00

Tender Premium Charge 5%								50000.00
PMC Charge 1%								10000.00
GST Charge 12%								120000.00
Miscellaneous and UnforessenCharges								1266.00
							Total	1000000.00
(Rupees Ten Lakhs Only)								

Assistant Engineer
Ward-15

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

ಪಂ. EE/DD/AS/78 ದಿನಾಂಕ: 18-19
18/12/18
ರೂ. Rs 10 to lakhs only
(Rupees Ten lakhs only)
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.

ಪಂ. EE/DD/TS/14 ದಿನಾಂಕ: 18-19
18/12/18
ರೂ. Rs 10.00 lakh only
(Rupees Ten lakhs only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ಪಲಯ, ಬೆಂಗಳೂರು